

10-24 4-061119

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,789-00-00
SE NE SE /4 SEC. 26, 10 S, 24 W
1650 feet from S section line
330 feet from E section line

Operator license# 5184

Lease: Cochran Well # 1

Operator: Shields Oil Producers, Inc.

County: Graham 127.89

Address: Shields Building
Russell, Kansas 67665

Well total depth 3935 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Shields Oil Producers, Inc. License# 5184

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 P.M. Day: 24 Month: October Year: 1997

Plugging proposal received from: Burt Beery

Company: Shields Oil Producers, Inc. Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
KANSAS CORP COM
10-30-97
1997 OCT 30 A 12:30

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 11:00 P.M., Day: 24, Month: October, Year: 1997


Actual plugging report:

- 1st. Plug at 2000' w/25 sxs. - Anhydrite 1961' - 2004'.
- 2nd. Plug at 1125' w/100 sxs. - Dakota 820' - 1120'.
- 3rd. Plug at 275' w/40 sxs. - Surface pipe 217'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs. - Mousehole with 10 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy plug: YES X NO
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2345 GL

I did [] / did not [X] observe the plugging.


(agent)
Form CP-2/3

INVOICED
DATE 11-5-97
INV. NO. 49433