

4-071146

SEP 26 1995

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,089 -00-00

SW SE SE /4 SEC. 31, 10 S, 24 W
330 feet from S section line
990 feet from E section line

Operator license# 4767

Lease: Hobbs "P" Well # 1-31

Operator: Ritchie Exploration, Inc.

County: Graham 74658

Address: 125 N. Market - #1000
Wichita, Kansas 67202
John Niernberger

Well total depth 2337 4510' feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 255 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 26 Month: September Year: 1995

Plugging proposal received from: Pete Forine

Company: Ritchie Exploration, Inc. Phone: 316-267-4375

Were: 8 5/8" - 255' S.P. cwc. w/N/A sxs cement. 5 1/2" casing set at 4510' w/N/A sxs cement. D.V. tool at 2312' cwc w/550 sxs cement. Elv. 2437' - Anhy. 2065' - Perfs 4229' - 3976'. Proposal - 350 sxs 60/40 pozmix - 8% gel and 5 sxs cotton seed hulls. Pump in 5 1/2" casing with pump truck - load both 5 1/2" casing and 5 1/2" x 8 5/8" annulus with cement top to bottom. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:30 P.M., Day: 26, Month: September, Year: 1995

Actual plugging report: Ritchie Exploration ordered 350 sxs 60/40 pozmix - 8% gel - 5 sxs. hulls. Pumped in with pump truck.

- 1. D.V. tool at 2312' cwc w/550 sxs cement.
- 2. Pumped in 5 1/2" casing w/20 sxs cement followed w/320 sxs cement w/5 sxs hulls. Max. P.S.I. 800#. S.I.P. 300#.
- 3. Pumped in annulus - would not take cement. Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED
STATE CORPORATION COMMISSION

10-6-95
OCT 6 1995

Remarks: Cemented by Allied Cementing - Russell, Kansas 67665

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X NO

Plugged through TUBING, CASING X Elevation: Wichita, Kansas GL

I did [X] / did not [] observe the plugging.

Marion J. Schmidt
(agent)

DATE OCT 10 1995

INV. NO. 43922