

4 060225

7-8

238
P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22 638-00-00

NE SW SE, SEC. 31, T 10 S, R 24 W/E
990 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Hobbs "P" Well # 2

Operator: Ritchie Exploration Inc.
Name & Address: 125 N. Market, Suite 1000
Wichita, KS 67202

County Graham 131.78

Well Total Depth 4055 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXX

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 30606

Address Wichita, KS

Company to plug at: Hour: 9:00PM Day: 8 Month: July Year: 19 91

Plugging proposal received from Lloyd Delett

(company name) Murfin Drilling Co. (phone) _____

were: Order 200 sxs. 60/40pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe

RECEIVED

7-29-91

JUL 29 1991

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXX

Operations Completed: Hour: 9:00P, Day: 8 Month: July Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2100' with 25 sxs. Anhydrite 2072-2112'

2nd plug at 1210' with 100 sxs. Dakota 910-1210'

3rd plug at 300' with 40 sxs. Surface pipe to 251'

4th plug at 40' with 10 sxs.

rathole with 15 sxs. mousehole with 10 sxs.

Remarks: Allied Cementing
(if additional description is necessary, use BACK of this form.)

INVOICED
(if necessary did not) observe this plugging.

DATE 8-13-91

REV. NO. 32690

Jub. S.

Signed 
(TECHNICIAN)

Herb Deines