

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21477-00-00
Spot: CSENE Sec/Twnshp/Rge: 34-10S-24W
2310 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: OTT Well Number: 1
County: GRAHAM Total Vertical Depth: 4325 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4288 200 SX CMT
Surface Casing Size: 8.625 feet: 287 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2003 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 04/04/2003 9:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1200' and 2065'.
Swaged onto 4 1/2" - mixed and pumped 210 sxs cement with 400# hulls.
Max. P.S.I. 600#. S.I.P. 500#.
Hooked up to 8 5/8" and pumped 90 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED
APR 10 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-10-03

INV. NO. 2003061405

APR 08 2003

GEAR PETROLEUM COMPANY, INC.
300 SUTTON PLACE
WICHITA, KS 67202

REPLACEMENT CARD

#1 OTT


34-10-24W
SE NE NE

CONTR RED TIGER DRILLING CO.

CTY GRAHAM

GEOL _____

FIELD GEYER EXT & CONF
(1/8 W)



ELV 2412 KB SPD 8/28/81 CARD ISSUED 7/1/82 IP P 96 BOPD & WTR
2407 GL LKC 3826-3828
API 15-065-21,477

LOG	Tops	Depth/Datum
ANH		2031 + 381
HEEB		3720-1308
TOR		3742-1330
LANS		3754-1342
STARK SH		3946-1534
BKC		3989-1577
L PAW		4108-1696
FT SC		4178-1766
MISS		4295-1883
RTD		4325-1913

8 5/8 " 287/180 SX; 4 1/2 " 4288/200 SX
DST (1) 3717-74 (TOR, LANS) / 30-60-45-90, REC 640' MW, SIP 1335-1322#, FP 100-170 / 194-334#
DST (2) 3825-38 (LKC) / 30-60-45-90, 362' GIP, REC 70' CL OIL, 186' HOCM, SIP 1053-1037#, FP 31-54 / 85-124#
DST (3) 3841-42 (LKC) / 30-30-30-30, REC 940' MW, SIP 1077-1077#, FP 85-295 / 350-475#
DST (4) 3887-3910 (LKC) / 30-60-45-90, REC MW (AMT NA), SIP 1227-1195#, FP 38-54 / 62-77#
DST (5) 3914-28 (STARK SH) / 30-60-45-90, REC 1550' CL GSY OIL, SIP 1152-1050#, FP 122-297 / 368-512#
DST (6) 3942-52 (STARK SH) / 30-30-30-30, REC 5' MUD, SIP 768-654#, FP 62-20 / 62-20#
DST (7) 3938-76 (STARK SH) / 30-30-30-30, REC 65' MUD, SIP 830-644#, FP 62-40 / 72-66#
DST (8) 4156-4234 (PAW, FT SC) / 30-30-30-30, REC 3' MUD, SIP 135-135#, FP 83-83 / 93-93#
MCT - CO, PF (LKC) 3826-28, AC 500 G, SWB 5 BO/1 HR. POP, P 96 BOPD & WTR, (GR 36°) - (KC PAY BEHIND PIPE)
INFO RELEASED: 2/23/84 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS