

4-23-87

6 030866

API NUMBER 15- 065-22,355 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 NE SE, SEC. 33, T 10 S, R 24 W/E

1980 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # Marmik Oil Co. #6875

Lease Name Alfreda Well # 1

Operator: 200 N. Jefferson # 500

County Graham 128.38

Name & Address El Dorado, Arkansas

Well Total Depth 3950 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cmt. Co. License Number

Address Plainville

Company to plug at: Hour: AM Day: 23 Month: 4 Year: 19 87

Plugging proposal received from Fred Barber

(company name) Marmik (phone)

were: 8 5/8 st @ 252' W/185 sx 4 1/2" set at 3948 with 140 sx Perf 3783, 3747, 3738

Order sand and Com Cmt. recover pipe order 200 sx Econolite and 5 sx hulls

Allied Cmt. Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 AM Day: 23 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT Dump sand on bottom to 3690 ' Spot 4 sx cmm cmt on sand and

recovered 3100 ' of 4 1/2" csg mix and pump 10 bbl cmt slurry followed with 5 sx hulls

mixed in with 180 sx cmt. slurry max. psi 750 # close in 150# psi Plug complete .

RECEIVED
STATE CORPORATION COMMISSION
5-11-87
MAY 11 1987

Remarks: (If additional description is necessary, use BACK of this form) CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 5-15-87

INV. NO. 16910

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow