

6-090446

10-3

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,591-00-00

E2 NW SW /4 SEC. 36, 10 S, 24 W
1980 feet from S section line
4290 feet from E section line

Operator license# 30287

Lease Ruder well # 2

Operator: Norwood Oil Company

County Graham

Address: 6602 Dublin Loop W. #1
Colorado Springs, Colorado
80918

Well total depth 4000 feet ^{130.00}
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 211 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas

Company to plug at: Hour: AM Day: 1 Month: October Year: 1990

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations phone: (913)483-5345

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 1990 feet with 25 sacks Rat hole: 10 sacks

2nd plug @ 1130 feet " 100 " Mousehole: sacks

3rd plug @ 260 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

5th plug @ feet "

Plugging Proposal Received by: Edwin A. Schumacher P.I.R.T. III

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 3:30 PM, Day: 3, Month: October, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 185sx 60/40 pozmix w/ 6% gel and 1 sx celloflake or flowcel.

Remarks: Elevation: 2355 GL, Anhydrite depth: 1976 - feet

Did not penetrate Arbuckle, cemented by Allied Cementing

I did did not[X] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
11-15-90
NOV 15 1990
CONSERVATION DIVISION

INVOICED

DATE NOV 16 1990

INV. NO. 29975

Ed Schumacher

Ed Schumacher P.I.R.T. III
(agent)