

R

6030387

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____
SESENE, SEC. 1, T 10 S, R 25 W/2
2970 feet from N/2 section line
330 feet from W/2 section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5046

Lease Name Richmeier Well # 1
County Graham 130.81

Operator: Raymond Oil Co. Inc.
Name & Address One Main Place, Ste. 900
Wichita, Kansas
67202

Well Total Depth 4025 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 194'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase Kansas 67524

Company to plug at: Hour: PM Day: 4 Month: 3 Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) _____

were: 8 5/8 st @ 194' w/ 130 ex 5 1/2 int @ 4024 w/ 150 ex Perf. 3979-85, 3999-4004

5 1/2 was squeezed no history.

Ordered 125 ex 50/50 pg 6% gel 3% cc

RECEIVED
STATE CORPORATION COMMISSION
3-28-85
MAR 28 1985

Plugging Proposal Received by Carl Goodnow
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 PM Day: 4 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Bottom plug 5 ex Cem. Sand. to 3900 5 ex Cem.

2 shots with no stretch - tied on to 5 1/2 - 8 5/8 Bannulus would not take any fluid. - Pumped down 5 1/2 with 6 ex gel hit 400* press. pumped 125 ex Cem mix @ 400* pump press. Shut in 400*.

No pipe recovered plugging complete.

Sen Cement Co.

Remarks: Old well no info. Fluid level was at perf
(If additional description is necessary, use BACK of this form.)

INVOICED
I did (not) observe this plugging.

DATE 4-3-85

Signed Carl Goodnow
(TECHNICIAN)

INV. NO. 7524

3-27-85
8