

6 030868

4-27-87 15-065-01898-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 7/28/30

NE NE, SEC. 03, T 10 S, R 25 W/E  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153  
Operator: Texaco, Inc.  
Name: Box 2420  
Address: Tulsa, Oklahoma 74102

Lease Name E.E. Fox Well # 1  
County Graham 138.61  
Well Total Depth 4265 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 212'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cmt. Co. License Number  
Address Plainville, Kansas

Company to plug at: Hour: PM Day: 27 Month: 4 Year: 19 87

Plugging proposal received from Earl Donaldson

(company name) Texaco Inc. (phone)

were: 8 5/8 @ 212' w/150 4 1/2 @ 4074 w/150 sk Perf 3805-12

3821-63 order 202 sx lite cement and 5 sx hulls

Allied Cmt. Co. Wellbrock Water Truck

Perf at 1350' w/2 S P F and at 2170' w/2 S P F.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5: PM Day: 27 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT Tubing parted @ 2325 stripped rods w/ pump parted in cage. Ran

in tubing to fish @ 2325 fluid in hole dropped when rods were pulled, through tubing

Mixed and pumped 100 sx cemt. mix. 5 sx hulls (60 bbl slurry) laydown to 1110' Circ. 70 sx.cmt.

Lay down 30 joints of 2 3/8" @ WOW. Weldon 4 1/2" collar. Mix and pump 3 sx hulls 100

sx cmt mix. 300# close in 150# psi Plug complete, on 8 5/8 - 4 1/2 Annulus.- Tie (onto) 4 1/2

Squeeze with 30 sx. cmt. Mix to 300# close in. Plug complete.

STATE CORP. COM. COMMISSION  
7-10-87

Remarks: CSG was cut off at 6' below surface (May 13) Cmt was there. JUL 10 1987

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(If done) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

DATE 7-13-87

INV. NO. 17484