

12-3

4-031878

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-20,996-00-00

SE NW SW /4 SEC. 03, 10 S, 25 W  
1650 feet from S section line  
4290 feet from E section line

Operator license# 5364 Lease Kuhn well # 1

Operator: Beren Corporation County Graham

Address: P.O. Box 723 Well total depth 4060 feet <sup>131.95</sup>  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 303 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Berexco, Inc. License# TAG-2269

Address: P.O. Box 723, Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 3 Month: December Year: 93

Plugging proposal received from: Bob Grant (Dennis Hamel KCC)

Company: Beren Corporation Phone: \_\_\_\_\_

Were: Order 300 sxs. 65/35 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Perf's at 1300' and 2168' - critical control shots.  
Order work string to plug.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 2:30 P.M., Day: 3, Month: December, Year: 93

Actual plugging report: 8 5/8" set @ 303' w/225 cwc. 4 1/2" set @  
4059' w/150 sxs. Perf. @ 3801' - 4011'. Ran tubing to 2218'.  
Mixed and pumped 115 sxs. to circulate. Pulled tubing. Squeezed 4 1/2"  
with total 240 sxs. cement blend with 300# hulls mixed in to Max. P.S.I.  
300#. Close in P.S.I. 200#. Squeezed 8 5/8" with 60 sxs. cement blend  
w/200# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I. 400#.  
Plug complete.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL \_\_\_\_\_

I  did not  observe the plugging.

*Carl Goodrow*

RECEIVED STATE CORPORATION COMMISSION

DEC 10 1993

(agent)

Form CP-2/3 CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE DEC 14 1993

INV. NO. 39504

12-3 FEB 23 1994