


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 36 Twp. 10 Rge. (E) 24(W)
Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner Petroleum, Inc.
Lease Name OWENS Well No. 1
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 27 1955
Application for plugging filed August 27 1955
Application for plugging approved August 27 1955
Plugging commenced August 27 1955
Plugging completed August 27 1955
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4130 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	222'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 210' and set first plug at 210'. Placed 1/2 sack hulls on top of plug followed by 20 sacks cement, mudded up to 40' and set second plug with 1/2 sack hulls on top of plug followed by 10 sacks cement to base of well cellar.

RECEIVED
STATE CORPORATION COMMISSION
9-10-55
SEP 10 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Karl E. Becker (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker
311 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 1955
My commission expires August 8, 1959
Gloria Morrison
Notary Public.



PLUGGING
FILE SEC 36 T 10 R 24
BOOK PAGE 146 LINE 41

WELL LOG

15-065-00734-00-00

COMPANY **Petroleum, Inc.**

SEC. **36** T. **10S** R. **21W**

FARM **OWENS** NO. **1**

LOC. **NE 1/4 RB**
330' FWL
330' FWL
 COUNTY **Grattan**

TOTAL DEPTH **4130'**

COMM. **August 16, 1955** COMP. **August 27, 1955**

CONTRACTOR **Carvey Drilling Company**

CASING **8-5/8" @ 222' w/110 cas.**

ELEVATION **2366' DF**
2369' RB

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

185	Surface Clay & Sand
222	Blue Shale
690	Shale & Shells
865	Shale and Sand
905	Sand
1790	Sand & Shale
1995	Shale & Shells
2029	Anhydrite
2135	Shale & Shells
2325	Shale
2560	Shale & Shells
3515	Shale & Lim
4130	Lim
N.T.D. 4130'	

Sample Tests

Topakas:	3475 (-1106)
Rechner:	3701 (-1332)
Toronto:	3718 (-1349)
Manning:	3736 (-1367)
Maraton Chert:	4106 (-1737)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 10 1955
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC-36-T-10-R-240
 BOOK PAGE 146 LINE 31

State of **KANSAS**
 County of **SEDGWICK**

I, **Karl E. Becker** of **Petroleum, Inc.**

upon oath state that the above and foregoing is a true and correct copy of the log of the **OWENS #1** well

Karl E. Becker

Subscribed and sworn to before me this **2nd** day of **September**, 19**55**.

Alexia M. ...
 NOTARY PUBLIC

My Commission Expires **August 8, 1959**

