

15-065-20528-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME Herman #1

WELL NUMBER #1

SPOT LOCATION NE NE SE

SEC. 1 TWP. 10 RGE. 25w (E) or (W)

COUNTY Graham

Date Well Completed \_\_\_\_\_

Plugging Commenced 10/2/85

Plugging Completed 11/4/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Chief Drilling Co., Inc.

ADDRESS 905 Century Plaza, Wichita, Ks. 67202

PHONE # (316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? \_\_\_\_\_  
Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4025'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	230, 11	none
				5 1/2"	4024'	1485'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3870' & 5 sacks cement. Shot pipe at 3104', 2912', 2721', 2513', 2330', 2214', 2020', 1813', & 1485'. Pulled 46 joints of pipe.

Plugged well with 3 hulls, 25 gel, 100 cement with 1 hull, 15 gel, 8 5/8 plug, & 80 sacks 60/40 poz 6% gel 3% c.c.

Plugging complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so-help me God.


(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 85

RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public [Signature]

My Commission expires:



NOV 7 1985  
11-07-85

WELL LOG

CHIEF DRILLING CO., INC.  
Suite 905 Century Plaza  
Wichita, Kansas 67202

#1 HERMAN  
NE NE SE Sec. 1-10-25W  
Graham County, Kansas

CONTRACTOR: Company Tools  
CASING RECORD: Set 230.11' 8 5/8"  
w/165 sacks Quick Set

COMMENCED: 2/20/72  
COMPLETED: 2/27/72

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand	0	245	2466 Gr.
Sand & Shale	245	1150	2468 D.F.
Shale	1150	1440	2471 K.B.
Shale & Sand	1440	1960	
Shale & Shells	1960	2109	
Anhydrite	2109	2143	
Shale & Shells	2143	2608	
Ft. Riley Lime	2608	2655	
Lime & Shale	2655	2830	
Shale & Lime	2830	3594	
Lime & Shale	3594	3831	
Lime	3831	3992	
Lime & Shale	3992	4025	
Total Depth	4025		

<u>FORMATION TOPS</u>			
Anhydrite	2109	+	362
Base Anhy.	2143	+	328
Heebner	3739	-	1268
Toronto	3761	-	1290
Lansing	3776	-	1305
T.D.	4025	-	1554


STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NE SE of Section 1-10-25W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*Jim Robinson*  
\_\_\_\_\_  
Jim Robinson, Office Manager

Subscribed and sworn to before me this 1st day of March, 1972.



*Virginia S. Fabian*  
\_\_\_\_\_  
Virginia S. Fabian, Notary Public