

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,615-00-00

LEASE NAME Herman

WELL NUMBER #1

1650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 1 TWP. 10S RGE. 25 (E1/4T1W)

COUNTY Graham

Date Well Completed 1/22/91

Plugging Commenced 1/22/91

Plugging Completed 1/22/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Weststar Resources, Inc.

ADDRESS P. O. Box 509, Purcell, OK 73080-0509

PHONE# (405)-527-3900 or OPERATORS LICENSE NO. 30063

(405)-527-5515

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-22-91 (date)

by Gibb Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4291'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	221'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4291'-2150' 10 sks cement @ 40'

20 sks cement @ 2150' 15 sks in rathole

100 sks cement @ 1325'

40 sks cement @ 750'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Weststar Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss, 1-25-91

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1991

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1991

GLEND A. R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-92 Commission Expires: February 6, 1992

Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

EMPHASIS OIL OPERATIONS

P. O. BOX 506
 RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Weststar Resources, Inc.
 P. O. Box 509
 Purcell, OK 73080-0509

CONTRACTOR: Emphasis Oil Operations
 Box 506
 Russell, KS 67665

LEASE: Herman WELL #1

LOCATION: SW NE SE
 Section 1-10S-25W
 Graham County, Kansas

LOGGERS TOTAL DEPTH: 4288'

ROTARY TOTAL DEPTH: 4291'

COMMENCED: 1/14/91

CASING: 8-5/8" @ 221' w/150 sks cement

ELEVATION: 2498' K.B.

COMPLETED: 1/22/91

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Dakota Sand	1191'	Heebner	3772'
Cedar Hills	1421'	Lansing-Kansas City	3808'
Red Bed	1900'	Base Kansas City	4036'
Anhydrite	2137'	Cherokee Shale	4225'
Red Bed	2173'	Cherokee Lime	4238'
Topeka	3556'	R.T.D.	4291'


STATE OF KANSAS)
) ss
 COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


 Kyle B. Branum

Subscribed and sworn to before me on January 24, 1991.

My commission expires: February 6, 1992.




 Glenda R. Tiffin, Notary Public
 STATE COMMISSION

JAN 25 1991

CONSERVATION DIVISION
 Wichita, Kansas