

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 3 Twp. 10S Rge. 25 (E) (W)

Location as "NE/CNW&SW&" or footage from lines 330 FWL 330 FSL of SE 1/4

Lease Owner Magnolia Petroleum Co.

Lease Name Elmer E. Fox

Well No. 1

Office Address Box 770, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3 - 22 19 59

Application for plugging filed (via telephone) 3 - 22 19 59

Application for plugging approved (via telephone) 3 - 22 19 59

Plugging commenced 3 - 22 19 59

Plugging completed 3 - 22 19 59

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Hill City, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 1235 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None				8-5/8"	238' KB Meas.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded 1235 to 600'; Halliburton plug @ 600', dumped 20 sx cmnt; cmnt & mud to 235';

Halliburton plug @ 235', dumped 20 sx cmnt; cmnt & mud to 40'; dumped 10 sx cmnt; mudded to surface.

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.

Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

C. O. Turner

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 770, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 19 59

Harriett S. Kaiser

Notary Public.

My commission expires January 14, 1961

Orig: KCC
cc: A. D. Fabricius
File

PLUGGING
FILE SEC. 3 T. 10 R. 25W
BOOK PAGE 27 LINE 35

DRILLERS' LOG

Well Owner: Magnolia Petroleum Company
 Farm Name: Fox Well No. 1
 Commenced: 3/10/59
 Completed: 3/22/59
 Total Depth: 4235'
 Casing: 8 5/8" @ 233' cemented
 Contractor: Peal Brothers, Inc.

SW SW SE
 Sec. 3-10S-25W
 Graham County, Kansas
 Elevation: 2491
 Production: Dry

Figures below indicate bottoms of formations:

Clay & sand	0 -	180
Blue shale		233
Shale & shells		535
Shale		1100
Sand & shale		1300
Shale		1725
Shale & red bed		2145
Shale		2160
Anhydrite		2195
Red bed & shale		2295
Shale & shells		2485
Shale & lime streaks		2530
Shale & broken lime streaks		2780
Lime		2905
Lime & shale		3015
Lime		3220
Lime & shale		3410
Lime		3600
Lime & shale		3700
Lime		4005
Lime & shale		4080
Cong.		4125
Lime & shale		4217
Lime		4235
Total Depth		4235

RECEIVED
 STATE CORPORATION COMMISSION
 APR 3 1959
 CONSERVATION DIVISION
 Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.


PEAL BROTHERS, INC.

BY Jack Matthews

SUBSCRIBED AND SWORN to before me this 24th day of March, 1959

My commission expires: April 27, 1960

Lucas Brack
 Notary Public



PLUGGING
 FILE SEC 3 T 10 R 25W
 BOOK PAGE 27 LINE 35