

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
260 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER \_\_\_\_\_

LEASE NAME: E. E. Fox

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NE

SEC. 3 TWP 10S RGE. 25 ~~XX~~ or (W)

COUNTY Graham

Date Well Completed 7-28-60

Plugging Commenced 4/24/87

Plugging Completed 4/27/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Texaco Inc.

ADDRESS P O Box 2420, Tulsa, OK 74102

PHONE # (918) 560-6000 OPERATORS LICENSE NO. 5/53

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hayes, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Toronto, Lans-KC Depth to top 3803-3818 bottom 3812-3963 T.D. 4265

Show depth and thickness of all water, oil and gas formations. PB 3978

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Toronto</u>		<u>3805</u>	<u>12</u>	<u>8 5/8</u>	<u>212</u>	<u>None</u>
				<u>4 1/2</u>	<u>4074</u>	<u>None</u>
<u>L-KC</u>		<u>3821</u>	<u>3963</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged from 3978' to 6' w/300 sacks cement through 4 1/2";  
from 212' - 6' through 8 5/8" w/100 sacks cement. From 6' to GL w/dirt weld on plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Company Tools License No. \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF Oklahoma COUNTY OF Tulsa, ss. STATE CORPORATION COMMISSION

D. L. Richter (employee of operator) or JUN 4 1987  
(operator) of above-described well, being first duly sworn on oath, says: That

I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God. CONSERVATION DIVISION  
Wichita, Kansas

(Signature) [Signature]

(Address) D. L. Richter  
P O Box 2420, Tulsa, OK 74102

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1987

[Signature]  
Notary Public



My Commission expires: 8-3-88

COMPANY ~~Herman~~ Geo. Kaiser, Oil Producer

SEC. 3 T. 10 R. 25  
 LOC. C NE NE 1/4


FARM Fox "A"

NO. 1

15-065-01898-00-00

TOTAL DEPTH 4265  
 COMM. 7/15/60  
 SHOT OR TREATED  
 CONTRACTOR H-30, INC.  
 ISSUED

COUNTY Graham



KANSAS

CASING  
 20 111  
 15 11 212'  
 12 6  
 13 5 1/2" at 4074'

ELEVATION 2539 K.B.

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface soil, sand & clay	170'
Shale	212'
Shale & shells	1655'
Shale with sand nicks.	2000'
Shale & shells	2190'
Anhydrite	2234'
Red sand & shale	2363'
Red sand & shells	2590'
Shale w/lime str.	2610'
Shale & lime	2765'
Shale & shells	2895'
Shale & lime	3655'
Lime	3714'
Lime & shale	3810'
<del>City</del> City Lime	3865'
Lime	3867'
<del>City</del> City Lime	3917'
Lime	3965'
<del>City</del> City Lime	3988'
Lime	4007'
<del>City</del> City Lime	4028'
Lime	4110'
<del>City</del> City Lime	4180'
Lime	4265'

FILE COPY

FORMATION TOPS:

Sample Tops

<del>Heel</del>	
<del>Lane</del>	3776 -1237
<del>Base</del>	3815 -1276
<del>City</del> City	4045 -1506
<del>City</del> City	4236 -1697
<del>City</del> City	4244 -1705
<del>Total</del>	4265 -1726

RECEIVED

HERMAN GEO. KAISER  
 OIL PRODUCERS

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By Merle Britting  
 Merle Britting

STATE OF KANSAS

COUNTY OF SEDGWICK } SS.

RECORDED  
 STATE CORPORATION COM.

FEB 17 1967

Subscribed and sworn to before me, a Notary Public, in and for said County of Sedgewick State this 29th day of July, 1960

CONVENTION OF NOTARIES  
 Wichita, Kansas

Rose Furey  
 Rose Furey, Notary Public

My commission expires February 13, 1964