


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 3 Twp. 10 Rge. 25W (E) (W)

Location as "NE/CNW&SW" or footage from lines SW-SW NW

Lease Owner Chief Drilling Co., Inc.

Lease Name Kuhn Well No. 1

Office Address Suite 905 Century Plaza, Wichita, Kans. 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed April 8, 1972 19

Application for plugging filed April 7, 1972 19

Application for plugging approved April 8, 1972 19

Plugging commenced April 8, 1972 19

Plugging completed April 8, 1972 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kans.

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4030 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	229'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged through drill pipe @ 1175' w/110 cubic ft. cement  
Plugged through drill pipe @ 450' w/30 cubic ft. cement  
Plugged through drill pipe @ 40' w/wood plug 1 1/4 sacks hulls & 10 cubic ft. cement.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 11 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson

Suite 905 Century Plaza, Wichita, Kansas  
(Address)



SUBSCRIBED AND SWORN to before me this 10th day of April, 1972

My commission expires August 5, 1975

Virginia S. Fabian  
Notary Public.

WELL LOG

CHIEF DRILLING CO., INC.  
 Suite 905 Century Plaza  
 Wichita, Kansas 67202

#1 KUHN  
 SW SW NW Sec. 3-10-25W  
 Graham County, Kansas

CONTRACTOR: Company Tools  
 CASING RECORD: Set 231' of 8 5/8"  
 w/150 sacks quick set cement

COMMENCED: 3/31/72  
 COMPLETED: 4/8/72

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Shale	0	235	2524 Gr.
Shale & Sand	235	1754	2526 D.F.
Sand	1754	1940	2529 K-B.
Shale & Shells	1940	2167	
Anhydrite	2167	2210	
Shale & Shells	2210	2350	
Lime & Shale	2350	2686	
Shale & Lime	2686	3035	
Lime & Shale	3035	3435	
Lime	3435	3969	
Lime & Shale	3969	4010	
Lime	4010	4030	
Total Depth	4030		

<u>FORMATION TOPS</u>		
Anhydrite	2174 +	355
Base Anhy.	2210 +	319
Heebner	3770 -	1241
Toronto	3790 -	1261
Lansing	3806 -	1277
R.T.D.	4030 -	1501

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 11 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW SW NW of Section 3-10-25W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*Jim Robinson*  
 \_\_\_\_\_  
 Jim Robinson, Office Manager

Subscribed and sworn to before me this 10th day of April, 1972.

*Virginia S. Fabian*  
 \_\_\_\_\_  
 Virginia S. Fabian, Notary Public

