

LEASE NAME Kuhn

WELL NUMBER 1

 Ft. from S Section Line

SE NW SW Ft. from E Section Line

SEC. 3 TWP. 10 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed

Plugging Commenced 12-3-93

Plugging Completed 12-3-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-3-93 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4060

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	313	8 5/8		None
	Casino	0	4059	4 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s.
 Perf at 2168' and 1300'. Run openended tubing to 2218.56'. Mix 50 sk. 65/35 pos, 10% 100# hulls. Pull 35 joints to 1125.23'. Mix 65 sk. 65/35 pos, 10% del, 100# hull. C late to surface. Pull tubing. Hook to 8 5/8. Mix 60 sk. 65/35 pos, 10% del, 200# hull Max. pressure 500#. Shut in 400#. Hook to 4 1/2. Mix 125 sk. 65/35 pos, 10% del, 100# hull Max. pressure 300#. Shut in 200#.

Name of Plugging Contractor Berexco, Inc. License No. 5364

Address Box 723 Hays, Kansas 67601

RECEIVED
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beren Corp. FEB 28 1994

STATE OF Kansas COUNTY OF Ellis, ss. CONSERVATION DIVISION
 Wichita, Kansas

Mr. Ted Crawford

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

NOTARY PUBLIC STATE OF KANSAS
 ROSEMARY SMITH
 My Appt. Exp. 5-1-1995

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

SUBSCRIBED AND SWORN TO before me this 14 day of December, 19 93

Rosemary Smith
 Notary Public

My Commission Expires: 5-1-1995

USE ONLY ONE SIDE OF EACH FORM