


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 3 Twp. 10SRge. 25W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
S/2 S/2 NW

Lease Owner Beren Corporation
Lease Name Kuhn "B" Well No. 1
Office Address 970 Fourth Financial Ctr., Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Dec. 6 19 78
Application for plugging filed (verbally) Dec 6 19 78
Application for plugging approved (verbally) Dec 6 19 78
Plugging commenced Dec 6 19 78
Plugging completed Dec 6 19 78
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4060'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to _____
feet for each plug set.

T.D. 4060'
Set 1st plug at 1100' with 70 sacks
2nd plug at 240' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks
Cemented with 50/50 posmix, 6% gel.
Plug was down at 3:00 a.m., 12-6-78.

RECEIVED
STATE CORPORATION COMMISSION
12-20-78
DEC 20 1978
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

SHERRIE L. BROOKS
Sedgwick County, Ks.
My Appt. Exp. 8-21-82

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of December, 19 78

My commission expires August 21, 1982

Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR:	Beren Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Kuhn "B" #1
LOCATION:	S/2 S/2 NW, Section 3-10S-25W Graham County, Kansas
SPUD DATE:	November 28, 1978
COMPLETION DATE:	December 06, 1978
	GR: 2517
	KB: 2522

0	309	Surface sand & clay
309	1749	Shale & sand
1749	2173	Sand & shale
2173	2209	Anhydrite
2209	2890	Shale
2890	3450	Shale & lime
3450	3980	Lime & shale
3980	4006	Lime
4006	4026	Lime & Shale
4026	4060	Lime
	4060	Rotary Total Depth

Spud hole at 5:00 p.m., November 28, 1978. Drilled 309' of 12 1/4" hole. Ran 7 joints of 8 5/8" - 28# casing. Set at 307' K.B. with 225 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 12:45 a.m., November 29, 1978.

T.D. 4060'. Set 1st plug at 1100' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 3:00 a.m., December 6, 1978.

SAMPLE TOPS:

Anhydrite 2174'
B/Anhydrite 2209'

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1978
CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Kuhn "B" #1, S/2 S/2 NW, Section 3-10S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 18th day of December, 1978.

 SHERRIE L. BROOKS
Sedgwick County, Ks
My Appt. Exp. 8-21-82

Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 8-21-82.