

15-065-30142-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 7 Twp. 10S Rge. (E) 25 (W)

Location as "NE/CNW/SW" or footage from lines CNE/4, NE/4, NW/4

Lease Owner Stoepelwerth Drilling, Inc. et al

Lease Name Mader Well No. 1

Office Address Box 193 Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Dec. 2, 1965 19

Application for plugging filed by phone Dec. 1, 1965 19

Application for plugging approved by phone Dec. 1, 1965 19

Plugging commenced Dec. 2, 1965 19

Plugging completed Dec. 2, 1965 19

Reason for abandonment of well or producing formation no indications of commercial production

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols Moreland, Kansas

Producing formation none Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dakota	water	1150	1650	8 5/8	211	0
Lansing	water	3826	4050			
Mississippian	water	4194	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with mud. Cement plugs displaced by Halliburton as follows: 20 sx @ 540' 20 sx @ 210' 10 sx @ 40'

RECEIVED
STATE CORPORATION COMMISSION

JAN 7 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Cementing Co.

Address Hill City, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.


George P Stoepelwerth II (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) GP Stoepelwerth
Box 193 Russell, Kansas 67665
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 1966

Anna Stearns Stoepelwerth
Notary Public

My commission expires April 9, 1968



DRILLERS LOG

STOEPPELWERTH DRILLING, INC.
RUSSELL, KANSAS

Well #1 Mader Commenced drilling 11-22-65
Location NE,NE,NW Sec 7, T10S, R25W Completed drilling 12-2-65
Graham County, Kansas
Surface casing 211' 8 5/8"

Formation Record:

Footage	Formation
0-190'	Sand & clay
190-1640'	Shale
1640-2184'	Sand & shale
2184-2240'	Anhydrite
2240-2580'	Shale & sand
2580-2610'	Anhydrite
2610-2810'	Shale, sand & lime
2810-3000'	Shale & lime
3000-3150'	Shale
3150-3375'	Lime & shale
3375-3430'	Shale
3430-4040'	Lime & shale
4040-4195'	Limey shale & sand
4195-4244'	Dolomite
4244' TD	

RECEIVED
STATE CORPORATION COMMISSION

JAN 7 1966

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above and foregoing is a true and accurate report of the drilling of the well described.

Date: January 2, 1966

[Signature]

State of Kansas

County of Russell



Subscribed and sworn before me, a Notary Public, this 2nd day of January 1966

[Signature]

My commission expires April 9, 1968