


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH

Locate well correctly on above
Section Plat

WELL PLUGGING RECORD

Graham County, Sec. 7 Twp. 10 Rge. 25 (E) W (W)
Location as "NE/CNW/SW" or footage from lines S/2 NW NE
Lease Owner Executive Petroleum Company
Lease Name McGuire Well No. 1
Office Address 1007 Denver U. S. National Center, Denver, Colorado 80202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-6-19-69
Application for plugging filed 10-6-19-69
Application for plugging approved 10-6-19-69
Plugging commenced 10-6-19-69
Plugging completed 10-6-19-69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE PIPE				8 5/8"	204'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st. plug was set @ 1280' with 70 sacks cement
2nd. plug was set @ 215' with 20 sacks cement
3rd. plug was set @ 40' with 10 sacks cement
Cementing to bottom of cellar

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.

Leo F. Dreiling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature)

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

Subscribed and sworn to before me this 13th day of October, 1969

My commission expires September 19, 1970

JOSEPH A. HESS

Notary Public.

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company Executive Petroleum Company
1007 Denver U. S. National Center
Denver, Colorado 80202

Sec. 7 Twp. 10 Rng. 25

Farm McGuire No. 1

Location S/2 NW NE

Total Depth 4030'

County Graham

Comm. 9-30-69 Comp. 10-6-69

Elevation: 2546' K. B.

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas 67671

2543' D. F.

2541' G. R.

Casing Record

Cement Record

Production:

204' - 8 5/8"

150 sacks cement

Figures Indicate Bottom of Formations

0'	60'	Top Soil & Sand
60'	130'	Yellow Clay
130'	170'	Clay
170'	1550'	Shale
1550'	2163'	Shale & Sand
2163'	2210'	Anhy.
2210'	2785'	Shale
2785'	3763'	Shale & Lime
3763'	4030'	Lime
4030'	T.D.	

STATE OF KANSAS)
COUNTY OF ELLIS)

I, Leo F. Dreiling of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your McGuire #1.

~~LEO F. DREYLING~~

Subscribed and sworn to before me this 13th day of October 1969.

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970