

15-179-00185-00-09


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

SHERIDAN County. Sec. 11 Twp. 10 Rge. (E) 30 (W)
Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner EMPIRE DRILLING COMPANY
Lease Name FINLEY Well No. 1
Office Address 650 FOURTH NATIONAL BANK BUILDING
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed NOVEMBER 21, 1957 19
Application for plugging filed NOVEMBER 21, 1957 19
Application for plugging approved NOVEMBER 21, 1957 19
Plugging commenced NOVEMBER 21, 1957 19
Plugging completed NOVEMBER 21, 1957 19
Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4610 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	SURFACE	0	224	8 5/8"	224	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


PLUG HOLE AT 750' WITH 20 SACKS CEMENT, 220' WITH 20 SACKS CEMENT AND 40' WITH 10 SACKS CEMENT

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 650 FOURTH NATIONAL BANK BUILDING

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD PARTNER (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Handwritten Signature]*
650 FOURTH NATIONAL BANK BUILDING (Address)



My commission expires JULY 2, 1958
SUBSCRIBED AND SWORN to before me this 25TH day of NOVEMBER, 19 57

RECEIVED
STATE CORPORATION COMMISSION

11-27-57
NOV 27 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 11 T 10 R 30W
BOOK PAGE 63 LINE 22

L O G

COMPANY: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 CONTRACTOR: EMPIRE DRILLING COMPANY, WICHITA, KANSAS
 FARM: FINLEY NO. 1
 LOCATION: NE NE NW SECTION 11-10-30 SHERIDAN COUNTY, KANSAS
 COMMENCED: NOVEMBER 9, 1957 ELEVATION: 2905 KB
 COMPLETED: NOVEMBER 21, 1957

0	TO	1440	SHALE AND SAND
1440	TO	2496	SHALE AND SHELLS
2496	TO	2530	ANHYDRITE
2530	TO	2970	SHALE AND SHELLS
2870	TO	3150	SHALE AND LIME
3150	TO	3295	SHALE AND SHELLS
3295	TO	3350	LIME AND SHALE
3250	TO	3388	SHALE AND LIME
3388	TO	3405	LIME AND SHALE
3465	TO	3555	LIME
3555	TO	3845	SHALE AND LIME
3845	TO	3990	LIME AND SHALE
3990	TO	4290	LIME
4290	TO	4355	LIME AND SHALE
4355	TO	4451	SHALE
4451	TO	4595	SHALE AND LIME
4595	TO	4610	LIME
		4610	RTD

SET: 3 5/8" 224' WITH 115 SACKS CEMENT

TOPS:

TOPEKA	3738
HEEBNER	3954
TORONTO	3977
LANSING KANSAS CITY	3993
BASE KANSAS CITY	4294
REWORKED MISSISSIPPIAN	4588

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE FINLEY NUMBER 1 NE NE NW SECTION 11-10-30, SHERIDAN COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 25TH DAY OF NOVEMBER, 1957.

Hazel Pierson
 HAZEL PIERSON, NOTARY PUBLIC

COMMISSION EXPIRES JULY 2, 1958

PLUGGING
 FILE SEC. 11 T. 10 R. 30W
 BOOK PAGE 63 LINE 22