

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22091-00-00  
Spot: NESESW Sec/Twnshp/Rge: 27-12S-16W  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: FROELICH B JI AND H Well #: 7  
County: ELLIS Total Vertical Depth: 3582 feet

Operator License No.: 6246  
Op Name: BENNETT & SCHULTE OIL CO., A GEN  
Address: 140 W WICHITA AVE  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3561	0	w/175 sxs cmt
SURF	8.625	217	0	w/150 sxs cmt <u>116.42</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/16/2008 11:00 AM  
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.  
Proposal Rcvd. from: FRANK SCHULTE Company: BENNETT & SCHULTE OIL COMPA Phone: (785) 483-2721

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Squeeze 1200' w/400 sxs; 200 sxs from top down.  
Perf Tech perf at 1885'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/16/2008 4:30 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

J&M Well Service RIH with tubing to 3406'.  
Allied rigged to tubing - pumped 6 sxs gel followed with 75 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in.  
Pulled tubing to 1885' - rigged to tubing - pumped 100 sxs 60/40 pozmix - 4% gel with 150# hulls.  
Pulled tubing to 950' - rigged to tubing - pumped 95 sxs 60/40 pozmix - 4% gel to circulate cement to surface.  
Pulled tubing.  
Topped off 4 1/2" casing with 5 sxs cement. Hole standing full.  
Pressured 8 5/8" casing to 1000# - instant pressure.

**Perfs:**

Top	Bot	Thru	Comments
3508	3511		
3458	3466		
3436	3438		
3398	3399		
3382	3386		
3326	3330		
3301	3305		
3224	3229		

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 29 2008  
CONSERVATION DIVISION  
WICHITA, KS

**INVOICED**

Remarks: ALLIED CEMENTING COMPANY-TICKET #35081.

Plugged through: TBG

DATE 11-6-08  
INV. NO. 2009060675

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

*[Handwritten initials]*

replacement card

BENNETT & SCHULTE OIL CO  
RUSSELL KS 67665

27-12S-16W  
NE SE SW

#7 FROELICH B. J. I. & H.


site 3-1/4 N & 7-1/2 E OF CATHERINE KS  
cont: SHIELDS DRILLING #1

cty: ELLIS  
fld: EMMERAM NE

API 15-051-22091

card:

fr date 09/22/1980    spd date 10/02/1980    drig comp 10/08/1980    card issued 03/05/1981    last revised 05/10/2004



ELV: 2090 KB, 2083 GL SMP	
tops.....	depth/datum
ANH.....	1238 +852
TOP.....	3032 -942
HEEB.....	3251 -1161
TOR.....	3270 -1180
LANS.....	3301 -1211
ARB.....	3561 -1471
RTD.....	3565 -1475
NO LOG	

**IP status:**  
OIL, P 10 BOPD & WTR, LKC 3324-3466 OA, ARB  
3561-3565 , 01/01/1981  
CORRECTION: 5/10/2004 - ORIG FR IN NE SE SE  
CSG: 8-5/8" 217 / 150 SX, 4-1/2" 3561 / 175 SX  
NO CORES  
DST (1) 3533-3565 (ARB), / 30-30-30-30, REC 90' OIL SPTD M  
(15% OIL) ISIP 931# FSIP 861# IFP 71# -81# FFP 81# -91#  
MICT - CO, (ARB OH), SWB DWN, SO, NAT, AC 750 GAL,  
SWB LD, SWB 1 BFPH (50% OIL), SET BP ABOVE ARB, PF  
(LKC) 3324-3466 OA, AC 12,000 GAL, SWB LD, SWB 1 BOPH  
& WTR, FULL BP, POP, IPP 10 BOPD & WTR, 1/1/1981,  
COMMINGLED

COPYRIGHT 2004  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS