

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19138-00-01  
Spot: NESWSE Sec/Twnshp/Rge: 10-31S-3E  
1087 feet from S Section Line, 1654 feet from E Section Line  
Lease Name: MOWDER Well #: 1  
County: COWLEY Total Vertical Depth: 3070 feet

Operator License No.: 9576  
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C  
Address: 8135 281ST RD  
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3049	946	35 SX
SURF	8.625	139		95 SX

*99.78*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2008 11:00 AM  
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.  
Proposal Rcvd. from: BRENT WHITEMAN Company: RON WHITEMAN DBA GEN-DOR O Phone: (620) 222-7808

Proposed Plugging Method: FILL WITH SAND TO 50' (2,999') ABOVE THE PERFS, DUMP BAIL 6 SACKS CEMENT ON TOP. SHOOT AND PULL PIPE, CIRCULATE CEMENT FROM 350' TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/21/2008 1:00 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

SANDED BACK @ 2,992', DUMP BAILED 6 SACKS CEMENT ON TOP. SHOT 5-1/2" CASING @ 946', LAYED DOWN CASING. RIH WITH TUBING @ 360', CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL AND DISPLACED IN CASING. SHUT DOWN 10-21-2008, TAGGED CEMENT @ 150'. RIH W/TBG @ 148., CONSOLIDATED MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL AND DISPLACED IN CASING. WAITED 2-1/2 HOURS AND TAGGED CEMENT @ 135'. RIH W/TBG @ 128, CONSOLIDATED MIXED & PUMPED 6 BBL GEL & HULLS, WELL WAS CIRCULATING AROUND, STARTED CEMENT AND HULLS, PUMPED 60 SXS 60/40 POZMIX 4% GEL, 1 SK HULLS, 35 CC. TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 1:00 P.M., 10-21-2008.

**Perfs:**

Top	Bot	Thru	Comments
3049	3059	OH	

RECEIVED  
KANSAS CORPORATION COMMISSION  
**OCT 29 2008**  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

Remarks: CONSOLIDATED CEMENT TICKET #19594.

Plugged through: TBG

DATE 11-6-08  
INV. NO. 2009060682

District: 02

Signed *Duane Krueger*  
(TECHNICIAN)

*PKJ*