

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21269-00-00
Spot: W2E2NE Sec/Twnshp/Rge: 10-31S-3E
3968 feet from S Section Line, 1067 feet from E Section Line
Lease Name: SATTERTHWAITE Well #: 3
County: COWLEY Total Vertical Depth: 3055 feet

Operator License No.: 9576
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C
Address: 8135 281ST RD
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3054	1836	75 SX
SURF	8.625	202		90 SX <u>99.29</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2008 2:30 PM
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.
Proposal Rcvd. from: BRENT WHITEMAN Company: RON WHITEMAN DBA GENDOR OI Phone: (620) 222-7808

Proposed Plugging Method: FILL WITH SAND TO 50' (2956') ABOVE PERFS, DUMP BAIL 6 SACKS CEMENT ON TOP. SHOOT AND PULL PIPE, CIRCULATE CEMENT FROM 350' TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/20/2008 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
SANDED BACK @ 2,958, DUMP BAILED 6 SACKS CEMENT ON TOP. SHOT 5-1/2" CASING @ 1836', LAYED DOWN CASING. RIH WITH TUBING @ 360', CONSOLIDATED MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4:00 P.M., 10-20-2008.

Perfs:

Top	Bot	Thru	Comments
3006	3010		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 29 2008
CONSERVATION DIVISION
WICHITA, KS

INVOICED

Remarks: CONSOLIDATED CEMENT TICKET #19595.
Plugged through: TBG

DATE 11-6-08
INV. NO. 2009060682

District: 02 Signed Duane Krueger
(TECHNICIAN)

PK