

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-30198-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 10-31S-3E  
160 feet from S Section Line, 2320 feet from E Section Line  
Lease Name: MOWDER Well #: 4  
County: COWLEY Total Vertical Depth: 3125 feet

Operator License No.: 9576  
Op Name: WHITEMAN, RON DBA GEN-DOR OIL C  
Address: 8135 281ST RD  
CAMBRIDGE, KS 67023

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3125	898	100 SX CMT
SURF	8.625	142		110 SX CMT <u>101-56</u>

Well Type: EOR UIC Docket No: E12927.2 Date/Time to Plug: 10/20/2008 8:00 AM  
Plug Co. License No.: 9576 Plug Co. Name: WHITEMAN, RON DBA GEN-DOR OIL CO.  
Proposal Rcvd. from: BRENT WHITEMAN Company: RON WHITEMAN DBA GENDOR OI Phone: (620) 222-7808

Proposed Plugging Method: FILL WITH SAND TO 50' (3,010') ABOVE THE PERFS, DUMP BAIL 4 SACKS CEENT ON TOP. SHOOT AND PULL PIPE, CIRCULATE CEMENT FROM 350' TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/20/2008 11:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 3,016, DUMP BAILED 5 SACKS CEMENT ON TOP. SHOT 4-1/2" CASING @ 898', LAYED DOWN CASING. RH WITH TUBING @ 360', CONSOLIDATED MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED. PLUG DOWN 1100, 10-20-2008. CONSOLIDATED CEMENT TICKET #19593.

Perfs:

Top	Bot	Thru	Comments
3064	3076		

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 29 2008  
CONSERVATION DIVISION  
WICHITA, KS

**INVOICED**

Remarks: DOCKET 33-12,927

DATE 11-6-08  
INV. NO. 2009060682

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

PKY