

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22131-00-00

Spot: NESESW

Sec/Twnshp/Rge: 31-18S-29W

935 feet from S Section Line, 2285 feet from W Section Line

Lease Name: RISLEY 'AB'

Well #: 1

County: LANE

Total Vertical Depth: 4630 feet

Operator License No.: 3988

Op Name: SLAWSON EXPLORATION COMPANY, I

Address: 204 N ROBINSON AVE STE 2300
OKLAHOMA CITY, OK 73102

String Size Depth (ft) Pulled (ft) Comments

SURF 8.625 329

WITH 225 SX CMT

150.48

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/13/2008 10:00 PM

Plug Co. License No.: 34190

Plug Co. Name: VISION OIL & GAS SERVICES LLC

Proposal Rcvd. from:

Company:

Phone:

Proposed Plugging Method: 1ST PLUG AT 2210' WITH 50 SX CMT. 2ND PLUG AT 1450' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: NONE

Date/Time Plugging Completed: 10/13/2008 12:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2210' WITH 50 SX CMT. 2ND PLUG AT 1450' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

INVOICED

DATE 11-6-08

INV. NO. 2009060694

RECEIVED
KANSAS CORPORATION COMMISSION


OCT 29 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Michael J. Maier
(TECHNICIAN)

Form CP-2/3