

6 090055

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20,719-00-00

SE 1/4, SEC. 21, T. 70 S, R. 27 W 1/2

1650 feet from NIS section line

990 feet from NIE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Schlyer Well # 1

Operator: Rain & Williamson Oil Co., Inc.

County Meriden

Name & Address 435 Page Court, 220 West

Well Total Depth 4050 131.62 feet

Douglas

Conductor Pipe: Size - feet -

Wichita, Kansas 67202

Surface Casing: Size 8 7/8 feet 268

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A

Other well as hereinafter indicated -

Plugging Contractor Rain & Williamson Oil Co., Inc. License Number 5146

Address 435 Page Court, 220 West Douglas Wichita, Kansas 67202

Company to plug at: Hour: - Day: 30 Month: January Year: 19 84

Plugging proposal received from Louis Borger

(company name) Rain & Williamson Oil Co., Inc. (phone) 316-265-9686

were: Order 180 sh. 50/50 permit, 6% gel, 3% Cal. Cl. +  
8 7/8" wiper plug, spot all plugs w/ drill pipe w/ heavy mud  
between all plugs

RECEIVED

STATE CORPORATION COMMISSION

FEB 21 1984

Plugging Proposal Received by Edwin A. Schumacher  
(TECHNICIAN)

02-21-1984

CONSERVATION DIVISION  
Wichita District Operations attended by Agent?: All - Part - None

Operations Completed: Hour: 6:30 AM Day: 30 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1<sup>st</sup> plug 2175' w/ 20 sh. cmt.

2<sup>nd</sup> plug 1273' w/ 100 sh. cmt. & 1 sh. Cello-Floke

3<sup>rd</sup> plug 320' w/ 40 sh. cmt.

4<sup>th</sup> plug 40' solid bridge 1 sh. bulk 10 sh. cmt.

10 sh. cmt. in rat hole

INVOICE  
Remarks: Chert - 2598', Anhydrite - 2174', Arbusch - no (sh)  
(If additional description is necessary, use BACK of this form.)

DATE 2-22-84 (did / did not) observe this plugging.

INV. NO. 0305

Signed Edwin A. Schumacher  
(TECHNICIAN)