

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179 - 20,765-00-00  
200' N SE SW Sec. 15, T 10S, R 28 (W/E)  
530 feet from SE N/S section line  
2970 feet from SE W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140  
Operator: Frontier Oil Company  
Name & 1720 Kansas State Bank Bldg.  
Address Wichita, Ks. 67202

Lease Name Bieker Well # 1  
County Sheridan  
Well Total Depth 4110 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8<sup>5/8</sup> feet 210

133.58

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling License Number 5302

Address Same as above;

Company to plug at: Hour: AM Day: 25 Month: September Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Mike Wagner

(company name) Red Tiger (phone) \_\_\_\_\_

were: Order 185 sks 50/50 pozmix 6% gel 3% cal. cl. 1 sk flo-cel and 8<sup>5/8</sup>" plug and 1 sk hulls. Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None XX

Operations Completed: Hour: 7:30 AM Day: 25 Month: September Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 2270 w/25 sks

2nd plug @ 1380 w/100 sks w/1 sk flo-cel

3rd plug @ 240 w/40 sks

4th plug @ 40 w/8<sup>5/8</sup>" plug 1 sk hulls and 10 sks cmt

10 sks in Rat Hole and 10 sks in Mouse Hole

Remarks: Cemented by Allied

RECEIVED  
STATE CORPORATION COMMISSION  
10-01-1984  
OCT 01 1984

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did\_/ did not) observe this plugging.

INVOICED

DATE 10-5-84  
INV. NO. 4049  
9-25

Signed Gibor P. Leiker  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

9-28-84  
28