

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05872-00-00
Spot: SESWNENE Sec/Twnshp/Rge: 23-11S-17W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: RUMSEY Well #: 31
County: ELLIS Total Vertical Depth: 3441 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 221 S BROADWAY STE 312
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	12	135		
PROD	4.5	3428	0	w/unknown sxs cmt
SURF	8.625	1140	0	w/unknown sxs cmt

111.83

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/27/2008 3:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PEISKER Company: ANDERSON ENERGY, INC. Phone: (316) 263-1006

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 800# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2008 3:35 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3030' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1500' - pumped 350 sxs cement with 400# hulls with good water circulation - no cement.
Ran out of cement - ordered another 250 sxs .
Pulled tubing to 1000' - pumped 250 sxs cement with 200# hulls - good circulation of water - no cement.
Ordered more cement.
Pulled tubing to 650' - pumped 225 sxs cement with 500# hulls - little circulation of cement - pulled tubing out - shut down.
10/28/2008 - Ran tubing in - tagged cement at 408' - LK Wireline shot perfs at 360' - pumped 50 sxs cement to circulate out the 4 1/2" - shut in 4 1/2".
Pumped 30 sxs to circulate out the 12" - shut in 12".
Pulled tubing out - topped off 4 1/2" with 5 sxs cement.
Plug complete.

Perfs:

INVOICED
DATE 11-7-08
INV. NO. 2009060698

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 03 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34930 AND #32234.

Plugged through: TBG

District: 04

Signed CMacmill
(TECHNICIAN)

CM

P.147

SHELL OIL CO

#31 RUMSEY

23-11-17W
SE SW NE NE

Contr.

ELLIS County

E 1941

Comm. 12-23-39

Comp.


1-14-40

IP

3000 BOPD

Tops	Depth	Datum
ANH	1135	
TOP	2856	
LANS	3155	
ARB	3427	
TD	3441	

Casing
 12" 135
 8" 1140
 4" 3428



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS