

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01405-00-00  
Spot: W2SWNW Sec/Twnshp/Rge: 27-8S-19W  
3300 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: GREEN A Well #: 3  
County: ROOKS Total Vertical Depth: 3433 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3432	0	w/unknown sxs cmt
SURF	8.625	180	0	w/unknown sxs cmt 111.57

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/29/2008 8:30 AM  
Plug Co. License No.: 33137 Plug Co. Name: GASCHLER WELL SERVICE LLC  
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Holes in casing 975' - 1315' - 1420' - 1550'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/29/2008 12:30 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Ran tubing to 1500' - pumped 200 sxs 60/40 pozmix - 4% gel with 300# hulls - had circulation.  
Pulled tubing to 750' - pumped 50 sxs 60/40 pozmix - 4% gel with 100# hulls - had circulation.  
Ran out of cement.  
Pumped another 75 sxs 60/40 pozmix - 4% gel to circulate to surface.  
Pulled all tubing - topped off casing with 5 sxs 60/40 pozmix - 4% gel.  
8 5/8" was checked on 10/08/2008 - it had been cemented.

**Perfs:**

**INVOICED**  
DATE 11-7-08  
INV. NO. 2009060700

RECEIVED  
KANSAS CORPORATION COMMISSION  
**NOV 03 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #2267.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

**OCT 31 2008**

PCT

W. L. Hartman

#3 Green A

27-8-19W  
W2 SW NW

Contr. W. L. Hartman

Rocks:

County

E 2007 Comm. 7-29-47 Comp. 10-17-47 IP 178 BOPD

Tops	Depth	Datum
RNH	1117	
TOP	2940	
HEEB	3117	
LANS	3183	
ARB	3431	
T. D.	3434	

Casing  
 8" 180  
 5" 3432  
 2700' OIH/9 hrs  
 Pmp 210 BO/12 hrs

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS