

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1974
03-22-1974
CONSERVATION DIVISION
Wichita, Kansas

15-065-20662-00-00

Operator's Full Name Murfin Drilling Company.

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Fritts Well No. 1

Location NW-SW-SW Sec. 17 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3660'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 7:30 AM Day 21 Month 3 Year 1974

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement
thru DP from 1000' to 675'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/22/74

INV. NO. 8787-W

Signed: H. L. Nichols
Well Plugging Supervisor