

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-065-00951-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE NW NW

SEC. 18 TWP. 10 RGE. 22

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Robinson "E"

Operator Petroleum Inc Address 311 E 3rd Wichita, Kans

Field _____ County Graham

Total Depth 4105 Feet.

Plugging Contractor Garvey Drg Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 258' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 650', displaced 20 sax cement through drill pipe, heavy mud to 250', set cementing plug and displaced 20 sax cement through drill pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement to bottom cellar.

Edward Letty

District Conservation Agent

Date 9-19-57

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1957
09-23-1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC. 18 T. 10 R. 22 W
BOOK PAGE 47 LINE 9