

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1961  
12-27-1961  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-065-00816-00-00

File No. \_\_\_\_\_ County: Graham

Location: SE SE SW Sec. 18 Twp. 10 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 22

Name of Field: \_\_\_\_\_ Total Depth: ~~48~~ 4078

I have this date completed supervision of plugging of:

Lease Name: Robinson Well No. 1

Operator's Full Name: Woodman & Iannitti

Complete Address: 714 Union Natl Bk Bldg Wichita, Kansas

Plugging Contractor Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated; \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2PM Day 17 Month 12 Year 61

The above well was plugged as follows:

8 5/8" 148' circulated with cement - 5 1/2" ~~478'~~ <sup>4078'</sup> with 100 sax cement behind,  
PB to 4066 - perf 4036'.

Filled with sand to 4010' - set 4 sax cement with dump bailer - pulled  
3632' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550',  
(35 sax Mud), displaced 20 sax cement through 5 1/2" at 550', heavy mud to  
220', displaced 20 sax cement through 5 1/2" at 220', heavy mud to 35', set  
rock and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co

Signed: Edna Petty  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INVOICED  
DATE 1-8-62  
INV. NO. 4245-W