

15-065-20104-00-00

Form CP-3  
Rev. 6-9-67

KANSAS

*JP*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 7 1967

12-7-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Dean and Clark, Incorporated,

Complete Address 416 Union Center Building, Wichita, Kansas.

Lease Name Schreiner Well No. 1

Location SW-SW-SE Sec. 27 Twp. 10 Rge. (E) (W) 24

County Graham Total Depth 4040

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 12:00 M Day 2 Month 12 Year 1967

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated.  
Dakota section from 1150' to 1350'.

Circulated hole with heavy mud. Pulled DP to 1365' and displaced 100 Sx. cement thru  
DP from 1365' to 1045'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 12/7/67

INV. NO. 6859-W