



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1964
07-15-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15065-19180-00-00

Dear Sir:

Mr. J. J. Wenrich of D & D Drilling Co. Inc., has this

date requested permission to plug the following described well:

Nadel & Gussman

Mr. Wenrich guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman

Complete Address: 625 Union Center, Wichita, Kansas.

Lease Name: Eaton Well No. 1

Location: NE-NW-SW Sec. 34 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3850 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wenrich was instructed to plug the well as follows:

228'--8 5/8" Surface pipe, cement circulated with 190 Sx.

Circulate hole with heavy mud, set plug @ 550' and 20 Sx, cement.

"	"	210' with $\frac{1}{4}$ sack hulls &
		20 Sx, cement.
"	"	40' with $\frac{1}{2}$ sack hulls &
		10 Sx, cement.

Very truly yours,

H. A. Nichols
Conservation Division Agent