

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

15-065-20668-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
CONSERVATION DIVISION
Wichita, Kansas
07-22-1974

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: P. O. Box #370, Hays, Kansas.

Lease Name: Turner Well No. 1

Location: 440' FNL & 1320' FWL-SW/4Sec. 7 Twp. 10 Rge. (E)(W)22

County: Graham Total Depth 4123' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Niernberger was instructed to plug the well as follows:

201'--8 5/8" Surface casing, cement circulated with 150 Sx.

Circulate hole with heavy mud. Pull DP to 1025' and displace 70 Sx.

cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

Very truly yours,

Leo J. Murray
Conservation Division Agent