



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

15-065-20302-00-00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 5 1970  
CONSERVATION DIVISION  
Wichita, Kansas

02-05-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Glen Vanaway of Quintin Little has this date requested permission to plug the following described well:

Mr. Vanaway guarantees payment of the plugging fee.

Operator's full Name: Quintin Little,

Complete Address: Box #1509, Ardmore, Oklahoma.

Lease Name: Holmquist-Holmes Well No. 1

Location: SW-SE-SW Sec. 12 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 4000' Oil Well

Gas Well  Input Well  SWD Well  D & A -X- Lost-Hole

Mr. Vanaway was instructed to plug the well as follows:

202'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

A. L. Nichols  
Conservation Division Agent