



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20381-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 - 1971
CONSERVATION DIVISION
Wichita, Kansas

07-06-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Sgg. Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Dussault Well No. 1

Location: NE-NE-NE Sec. 10 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

212'--8 5/8" Surface casing, cement circulated with 150 Sx.
381 1/4'--5 1/2" casing cemented on bottom with 75 Sx. Well plugged back to 3782'. Top perforations from 3736'-3742'.

Sand well back to 3725' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 135 Sx. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent