



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
5-12-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20442-00-00

Dear Sir:

Mr. L. O. Chubb of Cimarron Drillers, Inc., has this date requested permission to plug the following described well:

Mr. Chubb guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing Company,

Complete Address: 117 Cameron Building, Oklahoma City, Oklahoma.

Lease Name: Kuska Well No. 1

Location: SE-NW-NW Sec. 19 Twp. 10 Rge. (E)(W) 22

County: Graham Total Depth 1954' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Chubb was instructed to plug the well as follows:

NO SURFACE CASING (7 7/8" Hole).

Circulate hole from bottom with heavy mud. Pull DP to 875' and dis-  
place 100 Sx. cement thru DP. Pull DP to 275' and circulate cement  
to surface with 100 Sx.

Very truly yours,

*A. L. Nichols*  
Conservation Division Agent