

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Lease Operator: Anadarko Petroleum Corporation

Address: PO Box 1330 Houston, TX 77251-1330

Phone: (832) 636-8380 Operator License #: 4549

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Unknown (Date)

by: Ken Jehlik (KCC District Agent's Name)

Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No

Producing Formation(s): List All (If needed attach another sheet)

Krider Depth to Top: 2175' Bottom: 2260' T.D. 2365'

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15- 129-00316 - 00 - 00

Lease Name: Dean

Well Number: 1

Spot Location (QQQQ): - C - SW - NE

3300 Feet from [] North / [X] South Section Line

1980 Feet from [X] East / [] West Section Line

Sec. 1 Twp. 33 S. R. 41 [] East [X] West

County: Morton

Date Well Completed: 1956

Plugging Commenced: 09/04/2008

Plugging Completed: 09/05/2008

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put in, Pulled out. Contains data for Oil, Gas or Water Records and Casing Record.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Mixed 250 lbs hulls & 20 sks cmt & spot plug from 2175' to 1975'. Shot 4.5" csg loose @ 650' & pulled to 600'. Circulate hole w/mud. Mixed 40 sk cmt & spot plug from 600' to 400'. Pull 4.5" csg to 40'. Mix 8 sk cmt and plug from 40' - 0'. Cut off & capped 7" csg 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151

Address: Rt. 1 Box 49BA Tyrone, OK 73951-9731


Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

RECEIVED KANSAS CORPORATION COMMISSION

SEP 29 2008

Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well as duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.



(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 26th day of September, 2008

(Signature) Pamela A Frye My Commission Expires: 3/17/09

Notary Public

Handwritten initials 'PJT'