

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company LLC
Address: 125 N Market #1000, Wichita, KS 67202
Phone: (620) 886-5606 x27 Operator License #: 33168
Type of Well: Oil, Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Jeff Klock (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 095-20010-00-01
Lease Name: Westerman
Well Number: 1 OWWO
Spot Location (QQQQ): SW - NW - NE -
1010 Feet from North / South Section Line
2195 Feet from East / West Section Line
Sec. 33 Twp. 30 S. R. 9 East West
County: Kingman
Date Well Completed: 6-25-07
Plugging Commenced: 9-10-08
Plugging Completed: 9-15-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	249	
				4 1/2	4881	2180

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4260', bailed 4 sks cement, pulled slips, had 20" stretch, ripped casing at 3810', worked pipe, ripped casing at 3640', worked pipe, ripped casing at 3420', worked pipe, ripped casing at 3230', worked pipe, ripped casing at 3010', pipe came free, started out, pipe hung up, ripped casing at 2840', worked pipe, ripped casing at 2630', worked pipe, ripped casing at 2410', worked pipe, ripped casing at 2180', pipe came free, pulled casing up to 1500', pumped 35sks, 100# hulls, pulled up to 950', pumped 35 sks, pulled up to 300', circulated with 125 sacks to surface, pulled rest of casing, topped off with 15 sacks dry cement.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Woolsey Operating Company LLC

State of Ks County, Barber, ss.


Carl W. Dorr (Employee of Operator) or (Operator) on above-described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carl W. Dorr
(Address) P.O. Box 168 Medicine Lodge, KS 67104

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 03 2008

CONSERVATION DIVISION



SUBSCRIBED and SWORN TO before me this 1st day of October, 2008
Charlotte C. Hoagland My Commission Expires: 8/23/12
Notary Public

Handwritten initials