

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399
Phone: (785) 398-2270 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 09/19/2008 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4210 Bottom: 4217' T.D. 4217'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-23746-00-00
Lease Name: Casey
Well Number: 1-33
Spot Location (QQQQ): _____ - NW - NE - SW
2310 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 33 Twp. 17 S. R. 21 East West
County: Ness
Date Well Completed: 06/18/1993
Plugging Commenced: 09/19/2008
Plugging Completed: 09/19/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippian	Water & Oil	4204'	4217'	8 5/8"	237'	None
				4 1/2"	4204'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Swift Services pumped 225 sacks of 60/40 poz, 4% gel with 200# of hulls down 4 1/2" casing, filled casing top to bottom.
Shut in with 2000 psi and holding. 8 5/8 braden head was full of cement, unable to pump into. Job complete.

Name of Plugging Contractor: Swift Services, Inc License #: 32382
Address: N Highway 283, Ness City, KS 67560

RECEIVED
KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Ness, ss.

OCT 03 2008

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 210 W Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 2nd day of October, 2008
[Signature] My Commission Expires: 8-15-12
Notary Public



Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT