

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OCT 09 2008

Lease Operator: Pioneer Exploration, LLC  
Address: 15603 Kuykendahl, Suite 200, Houston, TX 77090  
Phone: (281) 893-9400 ext. 259 Operator License #: 32825

API Number: 15-055-21985-00-00  
Lease Name: Garden City  
Well Number: 7-20

Type of Well: D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): C - NW - NW - nw  
330 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line

The plugging proposal was approved on: 6/23/08 (Date)

Sec. 20 Twp. 22 S. R. 33  East  West  
County: Finney

by: Steve Durant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (if needed attach another sheet)  
Mississippi Depth to Top: 4710 Bottom: \_\_\_\_\_ T.D. 4950  
Chase Depth to Top: 2505 Bottom: 2591 T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 6/23/08  
Plugging Completed: 6/23/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Oil	0	335	8 5/8	335	0
Chase Group	Gas					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well plugged due to unrecoverable source lost down hole. One 2 Curie Cs 137 Source Abandoned 6-23-08 at 4950 feet.  
Hole filled w/ drill mud. set 50 sks (red dyed) cmt plug @ 4900  
50 sks cmt plug at 2400, 80 sks cmt plug at 1140, 40 sks cmt plug at 600, 50 sks cmt plug at 366. 20 sks cmt plug red dyed at 60'. cap well w/ state approved sign indicating last source down hole.

Name of Plugging Contractor: Warren Drilling, LLC License #: 33724  
Address: \_\_\_\_\_


Name of Party Responsible for Plugging Fees: Pioneer Exploration, LLC

State of Texas County, Harris, ss. Cynthia B. Gray

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Cynthia B. Gray

(Address) 15603 Kuykendahl, Suite 200, Houston, TX 77090



Subscribed and SWORN TO before me this 07 day of October, 20 08  
Clark Ordas My Commission Expires: DEC. 13, 2010  
Notary Public

PCT