

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Brungardt Oil & Leasing, Inc.
Address: PO Box 871, Russell, KS 67665
Phone: (785) 483-4975 Operator License #: 3956
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Darrel Pitman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-141-20,390-00-00
Lease Name: Meyer-Kellerman "A"
Well Number: 1
Spot Location (QQQQ): _____ -NW -SW -NE
1,450 Feet from North / South Section Line
2,460 Feet from East / West Section Line
Sec. 12 Twp. 10 S. R. 15 East West
County: Osborne
Date Well Completed: 9-25-08
Plugging Commenced: 9-26-08
Plugging Completed: 9-26-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	219'	Cmtd. w/165 sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run drill pipe to 1,130', pump 25 sax cement thru drill pipe; run drill pipe to 625', pump 100 sax cement thru drill pipe; run drill pipe to 270', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement in rat hole and 15 sax cement in mouse hole.

Name of Plugging Contractor: Shields Drilling Co. License #: 5184 RECEIVED KANSAS CORPORATION COMMISSION
Address: PO Box 709, Russell, KS 67665
Name of Party Responsible for Plugging Fees: Brungardt Oil & Leasing, Inc. OCT 08 2008
State of KANSAS County, RUSSELL, ss. CONSERVATION DIVISION WICHITA, KS

Burton Beery, Drilling Supt. Contractor (Employee of Operator or Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Burton Beery
(Address) PO Box 709, Russell, KS 67665


SUBSCRIBED and SWORN TO before me this 7th day of October, 2008

Ruth Phillips
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202




Shields

Russell, Kansas

WELL LOG

Operator: Brungardt Oil & Leasing, Inc.
 Well: Meyer-Kellerman "A" #1
 Commenced: 9-20-2008
 Completed: 9-26-2008
 Contractor: Shields Drilling Co.

Well Description: 1,450' FNL, 2,460' FEL
 NE/4 Sec. 12-10S-15W
 Osborne Co., KS



CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/165 sax

Elevation: 1,878' K.B.

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	550'
Sand	635'
Sand & redbed	1,116'
Anhydrite	1,147'
Redbed & shale	1,605'
Shale	2,650'
Shale & lime	2,950'
Lime	3,390' RTD

RECEIVED
 KANSAS CORPORATION COMMISSION

OCT 08 2008

CONSERVATION DIVISION
 WICHITA, KS

Notes