

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License # 5003

Type of Well: Oil Gas KCC PKT per CPZ13 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/10/08 (Date)

by: Jeff Klock (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Ft Scott Depth to Top: 4459' Bottom: 4464' T.D. 4657'
Miss Depth to Top: 4630' Bottom: 4640' T.D. 4657'

API Number 15-077-20182-00-01

Lease Name: RITTER "B" #1-10 KCC PKT

Well Number: #1-10

Spot Location (QQQQ): C NW NE

4620 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec 10 Twp 34 S. Rng. 8 East West

County: Harper

Date Well Completed: 8/30/82

Plugging Commenced: 8/28/08

Plugging Completed: 9/3/08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Contains casing record data for 8 5/8" and 4 1/2" casings.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

9/3/08: MIRU. Pulled 3420' of 4 1/2" production casing. Loaded hole with sand to 4410'. Ripped casing at 4410' and wouldn't come free. Ripped casing at 3420' and pipe came free. Pulled casing up to 1400' and pumped 35 sacks cement. Pulled casing up to 900' and pumped 35 sacks cement. Pulled casing up to 315' and pumped 105 sacks to surface. Pulled rest of casing. Total cement was 175 sacks of 60/40 pozmix and common with 4% gel.

Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 190th US 56 Highway, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel - Employee of Operator (Employee of Operator) or (Operator) on above-described well, Wichita, KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED KANSAS CORPORATION COMMISSION

OCT 08, 2008

CONSERVATION DIVISION WICHITA, KS

BRENT B. REINHARDT Notary Public - State of Kansas My Appt. Expires 12/7/2011

(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 6th day of October 20 08

Brent B Reinhardt Notary Public My Commission Expires: 12/7/2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT

