

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23160-00-00  
Spot: S2SWW Sec/Twnshp/Rge: 7-11S-18W  
367 feet from S Section Line, 4720 feet from E Section Line  
Lease Name: CAVE Well #: 16  
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3599	0	200 SX
SURF	8.625	330	0	175 SX

117-00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/27/2008 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEN BUELLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 700# hulls.  
Perfed at 600' - 1250' - 1850'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/27/2008 12:30 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Ran tubing to 3396' - spotted 75 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 2608' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1702' - pumped 165 sxs 60/40 pozmix - 4% gel with 100# hulls to circulate to surface.  
Pulled all tubing.  
Hooked onto backside and pressure to 500# immediately.  
Pumped down 5 1/2" casing with 25 sxs 60/40 pozmix - 4% gel.  
S.I.P. 400#.

**Perfs:**

Top	Bot	Thru	Comments
2964	3426		

INVOICED

DATE 9/24/08  
INV. NO. 2009060467

RECEIVED  
KANSAS CORPORATION COMMISSION  
**SEP 04 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

AUG 29 2008

*PKG*

ROBERT R. PRICE OPERATING, INC.  
 P.O. BOX 45442  
 TULSA, OK 74145

#16 CAVE


7-11-18W  
 C S/2 SW SW

CONTR RANGER DRILG. CO., INC.

CTY ELLIS

GEOL \_\_\_\_\_

FIELD COCHRAN WEST



ELV 1942 KB SPD 10/26/82 CARD ISSUED 3/3/83 IP P 6 BO & 87 BWPD  
 1937 GL LKC 3201-3426 OA  
 API 15-051-23,160

LOG	Tops .....	Depth/Datum	
			8 5/8 " 330/175SX; 5 1/2 " 3599/200SX
			CORE (1) 3098-3158 (TOP), REC 38', DETAILS NA
ANH .....	1292+	650	CORE (2) 3174-3234 (TOR, LANS), REC 50', DETAILS NA
TOP .....	2937-	995	CORE (3) 3234-3294 (LANS), REC 57', DETAILS NA
HEEB .....	3161-	1219	CORE (4) 3294-3354 (LANS), REC 59', DETAILS NA
TOR .....	3177-	1235	CORE (5) 3354-3394 (LKC), REC 32', DETAILS NA
LANS .....	3201-	1259	CORE (6) 3394-3434 (LKC), REC 7', DETAILS NA
BKC .....	3428-	1486	MICT - CO, PF (SHAW) 2964-3200 W/1 SPF, AC 7750G (28%
MARM .....	3450-	1508	HCL), SWB LD, NSO, PF (LKC) 3201-3426 OA W/1 SPF, AC 7750G
CONG .....	3464-	1522	(28% HCL), SWB LD, GSO, POP, P 6 BO & 87 BWPD (GR 27%), 2/
ARB .....	3533-	1591	5/83
LTD .....	3550-	1608	
RTD .....	3600-	1658	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS