

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-19047-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 2-28S-5W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: RITCHEY Well #: 1
County: KINGMAN Total Vertical Depth: 4556 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4396		300 SX
SURF	8.625	181		125 SX

148.07

Well Type: SWD UIC Docket No: D03656.0 Date/Time to Plug:
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: CARL W. DURR Company: WOOLSEY OPERATING CO.LLC Phone: (620) 886-5606

Proposed Plugging Method: CIBP AT 4270' W/ 2 SX, 35 SX AT 900', 35 SX AT 450'. THEN CIRC CMT FROM 250' TO SURFACE (PER STEVE VAN GIESON)

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/01/2008 11:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 4270' & 5 SXS CEMENT ON TOP OF BP, SHOT OFF PROD CASING @ 1304' AND PULLED 5.5 RAN 2.375 INTO 915' SPOTTED 35 SXS OF CEMENT, CAME UP TO 438' SPOTTED 35 SXS OF CEMENT, CAME UP TO 250' CIRCULATED CEMENT TO SURFACE USING 130 SXS OF CEMENT. 3/27/2008 GAS FLOWING UP THROUGH PLUGS, STARTED DRILLING OUT PLUGS TO REPLUG USING HEAVY MUD FOR SPACERS. 3/31/2008 PLACED MUD IN HOLE RAN TUBING INTO 915' SPOTTED 35 SXS COMMON W/CC, SPACED W/MUD SPOTTED CEMENT @ 377' AND CIRC TO SURFACE W/80 SXS OF COMMON AND CC, TAGGED WELL ON 4/1/2008 NO GAS AND ONLY FELL BACK 8'.

Perfs:

Top	Bot	Thru	Comments
4396	4566		
4352	4357		
4335	4339		

INVOICED
DATE 9/24/08
INV. NO. 2009060468

Remarks: ALLIED CEMENT, OUT OF MEDICINE LODGE KS, TICKET #31317

Plugged through: TBG

District: 02

Signed B. J. Hope

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 09 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

Handwritten initials