

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00149-00-02
Spot: SE Sec/Twnshp/Rge: 1-23S-37W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: FINKELSTEIN Well #: 2-1
County: KEARNY Total Vertical Depth: 2650 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2480		WITH 2 SX CMT
PROD	5.5	2647	0	WITH 200 SX CMT 86.13
SURF	10.75	260		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/06/2008 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2008 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG CIBP @ 2480' & 2 SX CMT. 2ND PLUG TEST CASING TO 500#.
PERFORATED AT 850'. RATE WAS 1250# @ .1 BPM. RE-PERFORATED @ 800. RATE
WAS 1.2 BPM @ 600#. MIXED & PUMPED 80 SX CMT & 150# HULLS & 70 SX CMT.
SHUT IN AT 1500#. 3RD PLUG PUMP 60 SX CMT DOWN ANNULUS. SHUT IN AT
450#.

Perfs:

Top	Bot	Thru	Comments
2632	2644		
2572	2596		
2548	2588		
2533	2543		


INVOICED
DATE 9/24/08
INV. NO. 2009060469

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 05 2008

Remarks: USED 60/40 POZMIX% GEL BY COPELAND.

Plugged through: CSG

District: 01



Signed _____

[Signature]

(TECHNICIAN)