

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-133-01561-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 30-27S-19E  
4221 feet from S Section Line, 1469 feet from E Section Line  
Lease Name: BRAZL *Brazl* Well #: BRA04  
County: NEOSHO Total Vertical Depth: 850 feet

Operator License No.: 0  
Op Name: LANDOWNER  
Address:

| String | Size | Depth (ft) | Pulled (ft) | Comments           |
|--------|------|------------|-------------|--------------------|
| PROD   | 2    | 800        |             |                    |
| SURF   | 8    | 20         |             | 20' is an estimate |

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/15/2007 8:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE Phone: (620) 431-9212

Proposed Plugging Method: Wash 2 cement strings to TD and fill from btm to top.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE  
Date/Time Plugging Completed: 08/15/2007 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 1" cement string was washed down the inside of the 2" pipe to 800'. A 1" cement string was washed down the outside of the 2" pipe to 215'. The well was plugged from btm to top thru these cement strings. A total of 90 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED  
KCC DISTRICT #3

SEP 16 2008 *AMD*

CHANUTE, KS

INVOICED  
DATE 10/8/08  
INV. NO. 2009060482

Remarks:

Plugged through: CSG

District: 03

Signed

*Alan Dunning*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 02 2008

CONSERVATION DIVISION  
WICHITA, KS