

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24827-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 2-19S-22W
390 feet from S Section Line, 1770 feet from E Section Line
Lease Name: R MOORE Well #: 1-2
County: NESS Total Vertical Depth: 4312 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4311	2179	WITH 150 SX CMT
SURF	8.625	225		WITH 160 SX CMT

140.14

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2008 5:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: SAND OFF 50' ABOVE PERFS & 2 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PLUG AT 650' WITH 70 SX CMT. PLUG AT 240' WITH 50 SX CMT. TOP OFF WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2008 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 4200' & 2 SX CMT. 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 70 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. PULLED CASING & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4272	4282		


INVOICED
DATE 10-17-08
INV. NO. 2009060521

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 22 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

[Handwritten signature]
PKT