

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23196-00-00
Spot: NESWSW Sec/Twnshp/Rge: 23-27S-21E
750 feet from S Section Line, 950 feet from W Section Line
Lease Name: WESTOFF Well #: A4-23
County: BOURBON Total Vertical Depth: 856 feet

Operator License No.: 33503
Op Name: PAXTON GRANT, LLC
Address: 132 N OTSEGO AVE
GAYLORD, MI 49735

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	857		95 SX CMT.
SURF	8.625	21		4 SX CMT.
T1	2.375	613		

35'

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/14/2008 9:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSET Company: W & W PRODUCTION CO. Phone: (624) 314-4223

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 857' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 08/14/2008 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:
THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1000 PSI. 75 SACKS OF CEMENT WERE PUMPED INTO THE WELL.

*Printed from RBDMS
Request from Wichita*

Perfs:

Top	Bot	Thru	Comments
519	522		

INVOICED
DATE 10-17-08
INV. NO. 2009060529

Remarks:
Plugged through:

District: 03 Signed Clayton P. Titel
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 22 2008
CONSERVATION DIVISION
WICHITA, KS
Form CP-2/3
PKT